


# SAPPHIRE WALL SYSTEM

Installation Guide



84"H-108"H





# Tools Needed for Installation

(Professional Assembly Recommended)









Chop Saw

Level

**Pry Bar** 

## **Quick Tips**

- 1. Unpack all product before assembly
- 2. Hang door last on install
- 3. 3 person installation
- 4. Make sure all panels are level
- **5.** Frame entire office and lock to wall before hanging tiles.
- 6. Professional installation recommended.
- 7. \*\*If your floor plan does not fit exactly with our sizes we suggest the following: A contractor may be hired to build out wall to meet measurements. This is called a knee wall and very common in the industry when odd measurements are left. This will make a finished look.





## **Identifying Parts**




1/2" Hex Bolts- for connectors

1" Hex Bolts- for panel to panel connectors


3" Hex Bolts- for wall starter



2" Sheet Metal Screws for top beam.



Top Beam




**Bottom Track** 



Spacer


Spacer Threaded and not Threaded



Wall Starter



Stack up Connector



Connectors



**End Trim** 



Frame



Panel Frame



Panel Topper- 10" Panel Topper- 20"










Laminate Fabric



Door and Frame



Glass Door Topper- 10" Glass Door Topper- 20" \*1/2" Bigger Than regular Glass





Light Blockers Small/Large





## **Example Images**










# Stacker Bracket Connectors

## Step 1: (for 95"H and 108"H only)

Attach glass topper to the wall system using the bracket shown (84"H wall system will not need a topper). **Please** attach stacker brackets and stacker frame before putting panels together.

# Above door glass is 1/2" larger



\*95"H wall system will have a 11"H topper

\*108"H wall system will have a 24"H topper




## SKUTCHI DESIGNS & R

# Installing Wall Starter and 1st Panel


## Step 2:

**Locate** the starting point of the project and install your first wall starter sleeve. After that is installed attach the wall starter post for your first frame. **Use 3 in hex bolts.** 




#### No pre-drilled holes.

Please use drill bolt and tap holes through frame. Then install sleeve on the wall



Fix the side groove into wall





\*If a connector needs to be attached to a wall, make pilot holes on the panel side and screw through the other side into the wall

\*Wall starters can

adjust up to 1"


Insert the side pole to the side groove. Side pole is processed as photo and fixed with panel connectors.





## Installing Door Against A Wall Starter

\*Note: Whenever you are installing a door directly against a wall starter, be sure to remove the threaded washers and replace them with unthreaded washers to connect the door properly.










## **Straight Connectors**

\*Make sure everything is level






## \*Assemble bottom track before attaching tiles to frame



Open bottom raceways

Slightly lift frame a half an inch

Slide L-shaped part track underneath frame. When finished connect back of track to Bottom of L-shaped part of track



Step 3:


Close raceways





## **Attaching Connectors**

into panels.




View Installation video here:

https://youtu.be/hPV8lzmqWQ4





# Attach End Trim to Wall system








## **Door Frame Assembly**

1. Arrange door frame pieces on the floor in the correct positions that they will be put together.



If installing on a connector, do not use gold clips, use sheet metal screws to be able to attach to panels


## Assembled Frame






\*When installing on connector please pre





Insert connector into top and side of frame and secure with screws








## **Installing Door Stabilizer**

# \*This must be done before installing the door frame on to the panels





Install a stabilizer on each panel that the door frame will be connecting to.

## To install stabilizer on to panel:

**Step 1:** Remove screws from panel



**Step 2:** Attach stabilizer on to panel with screws




**Step 3:** Attach stabilizer to floor by drilling directly into the floor and secure with screws








# Installing Swing Door Frame



\*Door frame on sliding door needs to be installed using sheet metal screws.

**5.** While tiles are off on 1 side of the wall, screw in through the panel to the frame with 1" hex bolts. 7ft walls this is the final step for the door frame assembly. 8ft walls need to be screwed in from the top as well.







## **Install Door Latch**


Follow this side if door edge is chiseled

renew mile tracin accor cago is crimorica


Step 1:



Follow this side if door edge is not chiseled  $\ lacktriangled$ 





Step 2:



Install drive-in collar


Step 3:

















## Step 1:

Insert slim rod into track of beam







Secure with screws


Slim rod






## **Sliding Door Assembly**


2. Place sliding door rail onto screwed in sliding door rail clips and screw in from below. Door rail must be placed 83 3/4" from the ground.




1. Screw in sliding door track directly into panel. Door rail must be placed 83 3/4" from the ground measuring from the bottom of the rail to the ground



3. Place sliding door bottom track on floor using double sided tape, velcro, or glue; Lining it up with the door rail. Then proceed to place in sliding door.




4. After inserting the sliding door into the rail, secure stopper on the end




**5.** Place sliding door



Locks are available on bottom only of sliding doors. **Spring** lock-a 1" deep hole must be drilled in floor to engage lock.





Parts:



**Track Clips** 

Screws



В

**Track Clips** 



Screws

Door Rail Stopper

D



Finish Caps








## Installing Door Frame Against Connector

1. When installing a door frame against a connector:

Remove the white clips from the connector.

3. Make sure its level


- 2. Use pre-drilled holes and screws to install
- 4. Install door after everything else is install









## Installing the tile hook
















## **Light Blockers**

Single sided by any connector. Double sided in between panels.







Electric/Data




#### FINAL CONNECTION IS DONE BY A LICENSED ELECTRICIAN


WARNING:


Risk of fire or electric shock. As with all non-directional systems, do not electrically connect panel to more than one supply source. Always determine that the panel is electrically connected to one and only one source of supply. Before using any equipment, check the entire system for polarity, continuity, and grounding integrity.





Click-Latch Device: When installing this system, ensure the connectors have securely clicked into position.





#### Power Supply Connection

The Power System is an eight wire system consisting of four individual circuits rated at 20 amps/120 volts maximum. Circuit 1 (black), circuit 2 (red), and circuit 4 (pink), are served by a system neutral (white) and an equpiment ground (green). Circuit 3 (blue) uses an isolated neutral (gray), and an isolated ground (green/yellow). The system may be supplied by a three phase power system with four individual circuits rated 20 amps/120 volts maximum, or as perimtted by local code.

When connecting electric pass throughs to power moduals, please make sure ARROW is up


#### **Outlet Layout Options**




OUTLET - BLANK - BLANK




OUTLET - OUTLET - BLANK




OUTLET - OUTLET - OUTLET



**OUTLET - DEDICATED\* - BLANK** 



OUTLET - DEDICATED\* - OUTLET



BLANK - DEDICATED\* - BLANK

\*PLEASE NOTE: Orange is used to represent the dedicated outlet. The actual color of the outlet is **black.** 

**EMERALD** Cubicles come with style #225 Outlets. **SAPPHIRE** Cubicles come with style #325 Outlets.





## Electric/Data





CAT 6 - Blank - Blank - Blank

#### DM2



CAT 6 - CAT 6 - Blank - Blank

#### DM3



CAT 6 - CAT 6 - CAT 6 - Blank

#### DM4



CAT 6 - CAT 6 - CAT 6

#### DM5



CAT 6 - Phone Jack - Blank - Blank

#### DM6



CAT 6 - CAT 6 - Phone Jack - Blank

#### DM7



CAT 6 - CAT 6 - Phone Jack

All Modules can be customized to customers specifications. Please call to review options with one of our sales representatives. Color of jacks may vary.

Choose to add additional acoustic to your system using this rockboard. Below are the test results of its performance.

#### ROCKBOARD® 40 - Acoustical Performance

	CO-EF		TM C 42 TS AT FI	23 REQUEN	NCIES		
Thickness	125 Hz	250 Hz	500 Hz	1000 Hz	2000 Hz	4000 Hz	NRO
1.0"	0.07	0.32	0.77	1.04	1.05	1.05	0.80
2.0"	0.26	0.68	1.12	1.10	1.03	1.04	1.00
4.0"	1.03	1.07	1.12	1.04	1.07	1.08	1.10

#### ROCKBOARD® 60 - Acoustical Performance

	00 55		TM C 42	23 REQUEN	IOIEC		
Thickness	125 Hz	250 Hz	500 Hz	1000 Hz	2000 Hz	4000 Hz	NRO
1.0"	0.08	0.33	0.78	1.03	1.02	1.04	0.80
2.0"	0.32	0.81	1.06	1.02	0.99	1.04	0.95

#### ROCKBOARD® 80 - Acoustical Performance

	CO EE	AS FICIEN	TM C 42		ICIES		
Thickness	125 Hz	250 Hz	500 Hz	1000 Hz	2000 Hz	4000 Hz	NRC
1.0"	0.11	0.31	0.82	1.01	1.02	1.01	0.80
2.0"	0.43	0.78	0.90	0.97	0.97	1.00	0.90

#### Environmentally Sustainable

Our stone wool production process uses some of the most advanced technology available. The last decade has seen a new generation of ROXUL manufacturing advancements designed to lower our environmental footprint. These endeavors have included:

- the capture and recycling of rainwater;
- reduction in energy consumption;
- recycling of raw materials back into the production process;
- the use of natural lighting in our facilities; and
- repurposing water used during the manufacturing process.

#### Moisture Resistance

ROCKBOARD®	Maiatura Caratian	<0.08%
40/60/80 ASTM C 1104	Moisture Sorption	(0.08%

#### Fungi Resistance

ROCKBOARD®	Determination of	Descod
40/60/80 ASTM C 1338	Fungi Resistance	Passed

#### Thermal Resistance

80	R-value/inch @ 75 °F	4.1 hr.ft <sup>2</sup> .F/BTU
77)	RSI value/25.4 mm @ 24 °C	0.72 m <sup>2</sup> K/W
60	R-value/inch @ 75 °F	4.2 hr.ft².F/BTU
77)	RSI value/25.4 mm @ 24 °C	0.72 m <sup>2</sup> K/W


#### Maximum Service Temperature

ROCKBOARD® 40/60/80	ASTM C 411	Hot Surface Performance In Compliance with ASTM C 612 @ 1200 °F (650 °C)
------------------------	------------	--

#### Fire Performance

ROCKBOARD® 40/60/80 CAN4 S114	Test for Non- Combustibility	Non-Combustible
ROCKBOARD® 40/60/80	Surface Burning	Flame Spread = 0
ASTM E 84(UL 723)	Characteristics	Smoke Developed = 0
ROCKBOARD® 40/60/80	Surface Burning	Flame Spread = 0
CAN/ULC S102	Characteristics	Smoke Developed = 0

## Temperature Development in a Standard Fire (ASTM E119)



### Compliance and Performance

ROCKBOARD® 40	Mineral Fiber Block and	Type IVA,
ASTM C 612	Board Thermal Insulation	Complies
ROCKBOARD®	Mineral Fiber Block and	Type IVB,
60/80 ASTM C 612	Board Thermal Insulation	Complies







## Installing the rockboard in the sapphire system.

Rockboard fits in between the laminate tiles on the system.





